

# ION GETTER PUMP CONTROLLER PINOUT SCHEMATIC & INTERFACE SPECIFICATION

GAMMA VACUUM DIGITEL (SPCe/QPC/MPCq) & AGILENT (IPCMini/4UHV) ELECTRICAL INTERFACE REFERENCE

|                      |                                              |                      |                                              |
|----------------------|----------------------------------------------|----------------------|----------------------------------------------|
| Document ID:         | SCH-ION-2021-082                             | Effective Date:      | December 18, 2021                            |
| Form Number:         | ELE-ION-F05 (Rev 2.0)                        | Review Cycle:        | Annual (12 Months)                           |
| Author / Created By: | Kadeem Manning, Tier II Facility Technician  | System Hardware:     | DIGITEL SPCe/QPC/MPCq & Agilent 4UHV/IPCMini |
| Connectors Covered:  | 10kV SHV, DB-9 (RS-232/485), DB-15 I/O Relay | Electrical Standard: | IEC 61010-1 / CE / Low Voltage Directive     |

## 1. High-Voltage Connector & Safety Interlock Architecture

**1.1 High-Voltage Power Connection (10kV SHV / SAFE-CONN):** Ion pump controllers deliver high DC potential (+3.0 kV to +7.0 kV DC for Diode CV / Differential DI elements; -7.0 kV DC for Triode TR elements) via co-axial 10kV SHV (Safe High Voltage) or SAFE-CONN receptacle assemblies. The connector outer braid provides a low-impedance ground return to the controller chassis. Disconnection automatically trips the internal high-voltage interlock loop.

| Terminal / Pin Name   | Connector Type         | Electrical Specification                          | Functional Signal Description                       | Safety Interlock Standard         |
|-----------------------|------------------------|---------------------------------------------------|-----------------------------------------------------|-----------------------------------|
| HV Output (+ / -)     | 10kV SHV Receptacle    | +3.0 to +7.0 kV DC (Diode)<br>-7.0 kV DC (Triode) | Anode/Cathode High Voltage DC Bias supply.          | Auto HV shutdown if unlatched     |
| Outer Braid Ground    | SHV Outer Bayonet      | Chassis Ground (< 0.1 Ω)                          | Low-impedance safety return & RF noise shield.      | Mandatory safety bond             |
| Safety Interlock Loop | 2-Pin Phoenix Terminal | 24V DC / 10 mA Optocoupled                        | External vacuum interlock / roughing valve contact. | Closed circuit required for HV ON |

## 2. DB-9 Female Serial Communications Interface (RS-232 / RS-485)

| Pin No. | Signal Designation        | RS-232 / RS-485 Mode | I/O Direction | Signal Specification & Logic Protocol         |
|---------|---------------------------|----------------------|---------------|-----------------------------------------------|
| Pin 1   | RS-485 Data- (D- / A)     | RS-485 Differential  | In / Out      | Inverted RS-485 differential data line.       |
| Pin 2   | RXD (Receive Data)        | RS-232 Serial        | Input         | Asynchronous serial data input from host PC.  |
| Pin 3   | TXD (Transmit Data)       | RS-232 Serial        | Output        | Asynchronous serial data output to host PC.   |
| Pin 4   | DTR (Data Terminal Ready) | RS-232 Control       | Input         | Handshake line from host controller.          |
| Pin 5   | GND (Signal Ground)       | Common Ground        | Reference     | Isolated signal ground reference point.       |
| Pin 6   | DSR (Data Set Ready)      | RS-232 Control       | Output        | Handshake signal indicating controller ready. |
| Pin 7   | RTS (Request To Send)     | RS-232 Control       | Input         | Hardware flow control request input.          |
| Pin 8   | CTS (Clear To Send)       | RS-232 Control       | Output        | Hardware flow control clear output.           |
| Pin 9   | RS-485 Data+ (D+ / B)     | RS-485 Differential  | In / Out      | Non-inverted RS-485 differential data line.   |

## 3. DB-15 Female Remote Analog, Relay Setpoint & EPO Interface

| Pin No.   | Terminal Name    | Signal Function & Type   | Electrical Range / Rating | Application & Interlock Behavior      |
|-----------|------------------|--------------------------|---------------------------|---------------------------------------|
| Pin 1 & 2 | Relay 1 NO / COM | Dry Contact Relay Output | 24V DC / 1.0 A Max        | Setpoint 1 process interlock trigger. |
| Pin 3 & 4 | Relay 2 NO / COM | Dry Contact Relay Output | 24V DC / 1.0 A Max        | Setpoint 2 UHV threshold indicator.   |

|             |                         |                          |                           |                                         |
|-------------|-------------------------|--------------------------|---------------------------|-----------------------------------------|
| Pin 5 & 6   | Remote HV Enable        | Optocoupled Input        | 12–24V DC / 15 mA         | External PLC closure turns HV ON.       |
| Pin 7 & 8   | Analog Out 1 (Pressure) | Logarithmic Analog Out   | 0.0 to 10.0 V DC (1V/dec) | Vout = 1.0V/decade log pressure output. |
| Pin 9 & 10  | Analog Out 2 (Current)  | Linear Current Monitor   | 0.0 to 10.0 V DC          | Proportional to measured ion current.   |
| Pin 11      | Chassis Ground          | Shield Ground Reference  | 0.0 V Reference           | Cable shield ground tie point.          |
| Pin 12 & 13 | External EPO Input      | Emergency Power Off Loop | Dry Contact Loop Closure  | Opening loop immediately disables HV.   |
| Pin 14 & 15 | Auxiliary 24V DC Out    | DC Power Supply Output   | +24V DC $\pm$ 5% / 250 mA | Power supply for external optocouplers. |

## 4. Wiring Harness Verification & Technician Certification

**Wiring Harness Verification Notes:** Interfacing wiring harness assembled for Gamma Vacuum DIGITEL SPcE quad controller in Bay 2 UHV testing station. Cable DB-15 pinout continuity verified using DMM. Logarithmic analog output 1 calibrated across 0–10 V DC range ( $1.00\text{V} = 1 \times 10^{-9}$  mbar;  $10.00\text{V} = 1 \times 10^0$  mbar). High-voltage interlock loop closed through chamber vacuum pressure switch. All pinouts and grounds verified by Kadeem Manning.

|                          |                       |                    |                             |
|--------------------------|-----------------------|--------------------|-----------------------------|
| Inspecting Technician:   | Kadeem Manning        | Role / Title:      | Tier II Facility Technician |
| Technician Signature:    | <i>Kadeem Manning</i> | Verification Date: | December 18, 2021           |
| Metrology Authorization: | Dr. Marcus Vance      | Harness Status:    | [ X ] APPROVED FOR SERVICE  |